Sl. No.	Description	Unit	Quantity	Tendered rate	
				Figures	Words
18	Constructing sinks complete with out-let pipes ..	No.	4		
19	Providing and fixing stone mortar and pestle ..	"	4		
20	Flooring with 3" lime concrete 1" cement concrete and top plastered with ½" thick cement plastering ..	Sqr.	8.00		
21	Levelling the ground all round	L.S.			Rs. 10
	For Constructing Latrine.				
1	Earthwork excavation and filling in basement, complete.	C.yd.	4		
2	Burnt stone in lime mortar foundation and basement ..	C.ft.	130		
3	Burnt brick in mortar superstructure	"	193		
4	Chunam plastering, 2 coats	Sqr.	4.91		
5	Cement pointing with thread lines	"	0.56		
6	White and colour washing, 2 coats	"	5.47		
7	Cement plastering ½" thick	"	0.80		
8	Tar washing, 2 coats	"	0.63		
9	Flooring with 3" lime concrete 1" cement concrete and top finished with ½" cement plaster .. .	"	0.38		
10	Fixing outlets, constructing drains, etc.	L.S.			Rs. 10
11	Providing galvanized iron sheet tubs 12"×6" complete with tarring	No.	6		

L. A. H. WINCKLEE,
Superintending Engineer.

Notification dated 7th November 1938.

Notice is hereby given that sealed tenders will be received at the Office of the Superintending Engineer, Electrical Department, Bangalore, upto 3 P.M. on the 28th November 1938, for constructing Electrical Quarters at Hoskote and Anekal. An approximate estimate of quantities is given below. These quantities are not guaranteed. The works should be completed by the end of February 1939.

2. The plans, detailed estimate and conditions may be seen at the office of the Superintending Engineer, Electrical Department, Bangalore, between the hours 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms, which may be obtained from the Superintending Engineer. The tenders should be accompanied by a statement in the form given below, showing the rate at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100 for buildings at Hoskote, and Rs. 100 buildings at Anekal, in cash or Government Promissory Notes, as earnest money and be superscribed "*Tender for constructing Electrical Quarters at Hoskote and Anekal,*" in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Superintending Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on the rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Public Works Department or those fixed by the Superintending Engineer, after working out data with not more than 10 per cent for the Contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of work, etc., and in all disputes of any kind, the decision of the Superintending Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific terms of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate, will not be accepted.

13. Charges on account of water, scaffolding materials, implements for setting out, barricading, clearing site, supply of work, etc., that may be found necessary during execution, will not be paid for separately, but should be borne by the Contractor.

Abstract estimate for the construction of a lower Subordinate's Quarters at Hoskote.

Serial No.	Items of work	Unit	Quantity	Estimated rate	Tendered rates in	
					Figures	Words
				Rs. a. p.	Rs.	Rs.
1	Earthwork excavations and filling in basement	C.yd.	33	0 3 3		
2	Concrete stone jelly in lime mortar foundation	C.f.	315	0 3 9		
3	Stone in clay foundation and basement including bond stones as per specification	,,	705	0 3 6		
4	Burnt brick in clay superstructure	,,	1,644	0 3 3		
5	Burnt brick in mortar superstructure	,,	400	0 4 3		
6	Burnt stone slabs 4" thick, roughly dressed and fixed in mortar	S.ft.	119	0 5 0		
7	Chunam plastering, 2 coats	Sqr.	42.22	3 0 0		
8	Cement pointing with thread lines	,,	1.00	3 4 0		
9	White and colour washing, 2 coats	,,	43.31	0 4 6		
10	Constructing sinks, complete	No.	1	5 0 0		
11	Providing and fixing stone mortar and pestle	No.	1	5 0 0		
12	Brick in mortar, 6" cornice	R.ft.	60	0 5 0		
13	Binding wall $1\frac{1}{8}' \times \frac{3}{4}'$ brick in mortar, with chunam plaster, etc., complete	No.	60	0 7 0		
14	First class Mangalore tile roofing on teakwood reepers 2"×1' including wood oiling to reepers	Sqr.	8.00	24 0 0		
15	Ventilating tiles set in cement mortar	No.	2	2 6 0		
16	Ridge tiles set in mortar and cement pointed	R.ft.	24	0 7 6		
17	T. W. wrought and put up with 2 coats of wood-oiling	C.ft.	32.20	5 8 0		
18	T. W. battened doors with 1" thick shutters and fixtures, etc., complete, as per drawing	S.ft.	156	1 8 0		
19	T. W. battened windows with 1" thick shutters of $\frac{5}{8}$" dia. iron bars and fixtures, etc., complete as per drawing	,,	78	1 12 0		
20	T. W. shelves, with shutters, planks, etc., complete	,,	48	1 4 0		
21	Chocolate painting, two coats	Sqr.	5.85	4 8 0		
22	Flooring with $1\frac{1}{2}$" thick cement concrete and $\frac{1}{2}$" cement plastering on the top, mixed with red ochre	,,	4.93	25 0 0		
23	Levelling the ground	L. S.	..	5 0 0		
	For Constructing a Latrine.					
1	Earthwork excavation and filling in basement, including watering and consolidating	C.yd.	3	0 3 3		
2	Burnt stone in lime mortar for foundation and basement, including bond stones, as per specification	C.ft.	90	0 4 6		
3	Burnt brick in lime mortar superstructure	,,	129	0 4 3		
4	Chunam plastering, $\frac{1}{2}$" thick	Sqr.	3.27	3 0 0		
5	Cement pointing with thread lines	,,	0.37	3 4 0		
6	White and colour-washing, two coats	,,	3.64	0 4 6		
7	Cement plastering, $\frac{1}{2}$" thick	,,	.52	10 0 0		
8	Tar-washing, 2 coats	,,	.42	2 8 0		
9	Flooring with 3" lime concrete, $1\frac{1}{2}$" cement concrete and cement plastering on tops.	,,	.55	22 0 0		
10	Fixing outlets, constructing drains, etc., complete	L. S.	..	5 0 0		
11	Providing galvd. iron sheet tubs 12"×6" complete with tarring	No.	3	0 12 0		

Abstract estimate for constructing a block of Two Linemen's Quarters at Hoskote and Anekal.

Serial No.	Items of work	Unit	Quantity	Estimated rate	Tendered rates in	
					Figures	Words
				Rs. a. p.	Rs.	Rs.
1	Earthwork excavation and filling in basement	C.yd.	16	0 3 3		
2	Concrete stone jelly in lime mortar foundation	C.ft.	176	0 3 9		
3	Stone in clay foundation and basement, including bond stones, as per specifications	,,	414	0 3 6		
4	Burnt brick in clay superstructure	C.ft.	853	0 3 6		
5	Burnt brick in mortar superstructure	,,	332	0 4 3		
6	Burnt stone slabs 4" to 6" thick roughly dressed and fixed in mortar	S.ft.	70	0 4 0		
7	Chunam plastering, 2 coats	Sqr.	24	3 0 0		
8	Cement pointing with thread lines	Sqr.	24	3 0 0		
9	White and colour washing, 2 coats	,,	1	3 4 0		
10	Roofing with first class Mangalore tiles on T. W. reepers 2"×1" including wood-oiling, two coats, to reepers	,,	9.16	24 0 0		
11	Ridge tiles set in mortar and cement pointed	R.ft.	25	0 7 6		
12	Ventilating tiles set in cement morter	No.	8	2 0 0		
13	T. W. wrought and put up with 2 coats wood-oiling	C.ft.	38.27	5 8 0		
14	T. W. battened doors with 1" thick shutters and all fixtures complete, as per drawing.	S.ft.	78	1 8 0		
15	T. W. battened windows with 1" thick shutters ⅝" dia. iron bars and all fixtures, complete, as per drawing	,,	45	1 10 0		
16	T. W. shelves with battened shutters, planks, frame 3"×4", etc.	,,	30	1 4 0		
17	Chocolate painting, 2 coats	Sqr.	4	4 8 0		
18	Constructing sinks	No.	2	5 0 0		
19	Providing stone mortar and pestle	No.	2.	5 0 0		
20	Flooring with 1½" cement concrete on 3" lime concrete and ½" thick cement plaster on top	Sqr.	4	20 0 0		
21	Levelling ground	L. S.	..	5 0 0		
22	Chunam borders 6"×3" at the end of roof	R.ft.	32	0 3 0		
	Constructing Latrines.					
1	Earthwork excavation and filling in basement, including watering and consolidating	C.yd.	3	0 3 3		
2	Burnt stone in lime mortar foundation and basement, as per specification	C.ft.	90	0 4 6		
3	Burnt brick in lime mortar superstructure	C.ft.	129	0 4 3		
4	Chunam plastering, ½" thick	Sqr.	3.27	3 0 0		
5	Cement pointing with thread lines	,,	.37	3 4 0		
6	White and colour washing, 2 coats	,,	3.64	0 4 0		
7	Cement plastering, ½" thick	,,	.52	10 0 0		
8	Tar washing, 2 coats	,,	.42	2 8 0		
9	Flooring with 3" lime concrete, 1½" cement concrete and cement plaster	,,	.55	20 0 0		
10	Fixing outlets, constructing drains, etc., complete	L. S.	..	5 0 0		
11	Providing galvd. iron sheet tubs, 12"×6" complete, with tarring	No.	3	0 12 0		

M. HAYATH,
For *Superintending Engineer.*